



MAIN ST. CULVERT REPLACEMENT

**PROJECT NO. 2023-024
BID NO. 2682**

ADDENDUM 1

June 23, 2025

To all bidders:

1. BID FORM:

- Replace Bid Form in Exhibit A with the following:

EXHIBIT A – BID FORM (REVISED)**Main St. Culvert Replacement - Project No. 2023-024**

No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
1	800	Mobilization	1	LS		
2	801	Construction Surveying	1	LS		
3	SP-01	Traffic Control	1	LS		
4	SP-02	Comprehensive Grading	1	LS		
5	SP-03	Select Material	2600	TN		
6	SP-04	Borrow Excavation	100	CY		
7	SP-05	Rock Removal	100	CY		
8	226	Undercut Excavation	100	CY		
9	300	Foundation Conditioning Material, Minor Structures	70	TN		
10	300	Foundation Conditioning Geotextile	500	SY		
11	SP-07	8' X 9' Precast Reinforced Concrete Culvert	80	LF		
12	SP-08	Precast Modular Block Gravity Retaining Wall, Strong Stone or eq.	780	SF		
13	SP-09	Non-standard Toewall	2	CY		
14	SP-09	Additional Concrete for Toewall	10	CY		
15	610	Surface Course S 9.5B	30	TN		
16	610	Intermediate Course I 19.0C	25	TN		
17	610	Base Course B 25.0C	80	TN		
18	620	Asphalt Binder for Plant Mix	7	TN		
19	607	Incidental Milling	100	SY		
20	654	Asphalt Plant Mix, Pavement Repair	36	TN		
21	846	2'-6" Concrete Curb & Gutter	200	LF		
22	848	4" Concrete Sidewalk	15	SY		
23	SP-10	Concrete Steps	0.7	SY		
24	848	6" Concrete Driveway	8	SY		

No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
25	858	Adjustment of Manholes	1	EA		
26	858	Adjustment of Valve Boxes	3	EA		
27	SP-11	Flowable Fill for Storm Pipe Abandonment	10	CY		
28	SP-12	Stream Pump Around Operation	1	LS		
29	SP-14	No.57 Stone for Steam Structures	100	TN		
30	SP-14	Boulder	75	TN		
31	SP-14	Rip Rap, Class A	20	TN		
32	876	Rip Rap, Class 1	25	TN		
33	876	Geotextile for Drainage	500	SY		
34	1605	Temporary Silt Fence	120	LF		
35	SP-17	Coir Fiber Matting	750	SY		
36	SP-18	Storm Drain Inlet Protection	11	EA		
37	SP-19	Safety Fence	300	LF		
38	SP-20	8" Compost Filter Sock	140	LF		
39	1631	Matting for Erosion Control (Biodegradable Netting)	1500	SY		
40	1660	Seeding and Mulching	0.7	AC		
Storm Sewer						
41	305	24" RCP Storm Pipe (Class III)	260	LF		
42	305	24" RCP Storm Pipe (Class IV)	111	LF		
43	305	24" DIP Storm Pipe	22	LF		
44	305	18" RCP Storm Pipe (Class III)	29	LF		
45	305	18" RCP Storm Pipe (Class IV)	66	LF		
46	305	15" RCP Storm Pipe (Class III)	362	LF		
47	310	18" Pipe End Section	1	EA		
48	840	Masonry Drainage Structures, Std. 840.01	4	EA		
49	840	Masonry Drainage Structures, Std. 840.01 - Additional Depth	5	LF		

No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
50	840	Masonry Drainage Structures, Std. 840.05	3	EA		
51	840	Masonry Drainage Structures, Std. 840.15	4	EA		
52	840	Masonry Drainage Structures, Std. 840.32	4	EA		
53	840	Masonry Drainage Structures, Std. 840.32 - Additional Depth	17	LF		
54	840	Masonry Drainage Structures, Std. 840.34	2	EA		
55	840	Masonry Drainage Structures, Std. 840.34 - Additional Depth	2	LF		
56	840	Frame with Grate and Hood, Std 840.03 Type E	4	EA		
57	840	Frame with Grate, Std 840.16	4	EA		
58	840	Frame with Cover, Std 840.54	6	EA		
59	840	Frame with Cover, Std 840.55	3	EA		
60	840	Pipe Collar, Std 840.72	0.75	CY		
61	859	Convert Existing Hidden Box to Junction Box	1	EA		
Guardrail						
62	862	Steel Beam Guardrail	125	LF		
63	862	Steel Beam Guardrail, Shop Curved	37.5	LF		
64	862	Guardrail End Units, Type TL-2	2	EA		
65	862	Guardrail End Units, Type AT-1	1	EA		
Water Line Replacement						
66	WSACC	6" DIP Water Pipe	70	LF		
67	WSACC	6" 45-degree DIP Bend	4	EA		
68	WSACC	6" 90-degree DIP Bend	2	EA		
69	WSACC	8" DIP Water Pipe	120	LF		
70	WSACC	8" 45-degree DIP Bend	6	EA		
71	WSACC	8" x 6" Tee DIP	1	EA		
72	WSACC	8" TEAM Insertion Valve w/ Valve Box	2	EA		

No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
73	WSACC	3/4" Residential Water Service - (City to Provide Meter Box if needed)	8	EA		
74	SP-21	Plumbing Permit and Requirements for Reconnecting Water Services	7	EA		
75	SP-21	Plumbing Permit and Requirements for Reconnecting Water Services (624 Main St.)	1	EA		
76	SP-22	6" Connection to Ex. 6" Water Main - Transition Fittings	1	EA		
77	SP-22	8" Connection to Ex. 8" Water Main - Transition Fittings	2	EA		
78	SP-22	Temporary 6" Connection to Ex. 6" Water Main - Tapping Sleeve and Valve	1	EA		
Sewer Line Replacement						
79	WSACC	Sanitary Sewer Bypass Pumping	1	LS		
80	WSACC	8" P401 Lined DI Sanitary Sewer Pipe	90	LF		
81	WSACC	8" x 6" P401 Lined DIP Reducer	1	EA		
82	WSACC	4" Sewer Lateral	2	EA		
83	WSACC	Tie to Sanitary Sewer System	1	LS		

TOTAL BASE COST \$ _____

10% CONTINGENCY \$ _____

TOTAL COST \$ _____