

COUNTRY CLUB DR. CULVERT REPLACEMENT

**PROJECT NO. 2021-043
BID NO. 2561**

ADDENDUM 1

November 8, 2022

To all bidders:

1. BID FORM:

- Replace Bid Form in Exhibit A with the following:

EXHIBIT A – BID FORM (REVISED)

Country Club Dr. Culvert Replacement - Project No. 2021-043

No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
1	800	Mobilization	1	LS		
2	801	Construction Surveying	1	LS		
3	SP-01	Traffic Control	1	LS		
4	SP-02	Comprehensive Grading	1	LS		
5	SP-03	Select Material	4600	TN		
6	SP-04	Borrow Excavation	100	CY		
7	SP-05	Rock Removal	100	CY		
8	225	Undercut Excavation	100	CY		
9	300	Foundation Conditioning Material, Minor Structures	100	TN		
10	300	Foundation Conditioning Geotextile	400	SY		
11	SP-07	12' X 11' Precast R.C. Culvert	156	LF		
12	SP-08	Precast Modular Block Gravity Retaining Wall, Strong Stone	1250	SF		
13	SP-09	Non-standard Toewall	7.5	CY		
14	610	Surface Course S 9.5B	260	TN		
15	610	Intermediate Course I 19.0C	160	TN		
16	610	Base Course B 25.0C	100	TN		
17	620	Asphalt Binder for Plant Mix	30	TN		
18	520	Aggregate Base Course	550	TN		
19	607	Incidental Milling	100	SY		
20	654	Asphalt Plant Mix, Pavement Repair	15	TN		
21	846	2'-6" Concrete Curb & Gutter	580	LF		



No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
22	848	6" Concrete Driveway	95	SY		
23	858	Adjustment of Manholes	1	EA		
24	858	Adjustment of Valve Boxes	1	EA		
25	SP-10	Stream Pump Around Operation	1	LS		
26	876	Rip Rap, Class B	120	TN		
27	876	Rip Rap, Class 2	260	TN		
28	876	Geotextile for Drainage	600	SY		
29	SP-12	Coir Fiber Matting	540	SY		
30	1605	Temporary Silt Fence	150	LF		
31	1610	Stone for Erosion Control, Class B	50	TN		
32	1610	Sediment Control Stone	15	TN		
33	SP-13	Storm Drain Inlet Protection	4	EA		
34	SP-14	Safety Fence	900	LF		
35	1631	Matting for Erosion Control (Biodegradable Netting)	1500	SY		
36	1660	Seeding and Mulching	1.1	AC		
Storm Sewer						
37	305	18" RCP Storm Pipe (Class III)	119	LF		
38	305	24" RCP Storm Pipe (Class III)	154	LF		
39	305	24" RCP Storm Pipe (Class IV)	72	LF		
40	310	24" P.C. Cross Pipe End Section	1	EA		
41	840	Masonry Drainage Structures, Std. 840.01	6	EA		
42	840	Masonry Drainage Structures, Std. 840.01 - Additional Depth	13.2	LF		
43	840	Masonry Drainage Structures, Std. 840.05	2	EA		



No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
44	840	Masonry Drainage Structures, Std. 840.32	2	EA		
45	840	Masonry Drainage Structures, Std. 840.32 - Additional Depth	0.8	LF		
46	840	Frame with Grate and Hood, Std 840.03 Type F	1	EA		
47	840	Frame with Grate and Hood, Std 840.03 Type G	1	EA		
48	840	Frame with Grate and Hood, Std 840.03 Type E	4	EA		
49	840	Frame with Cover, Std 840.54	2	EA		
50	SP-15	Flowable Fill for Storm Pipe Abandonment	5	CY		
Guardrail						
51	863	Steel Beam Guardrail	162.5	LF		
52	863	Steel Beam Guardrail, Shop Curved	25	LF		
53	863	Additional Guardrail Post	5	EA		
54	863	Guardrail End Units, Type TL-2	2	EA		
55	863	Guardrail End Units, Type CAT-1	1	EA		
56	863	Guardrail End Units, Type AT-1	1	EA		
Water Line Replacement						
57	WSACC	6" Restrained DIP Water Pipe	30	LF		
58	WSACC	6" 45-degree DIP Bend	4	EA		
59	WSACC	8" Restrained DIP Water Pipe	220	LF		
60	WSACC	8" 45-degree DIP Bend	9	EA		
61	WSACC	8" x 8" x 8" DIP Tee	1	EA		
62	WSACC	8" x 6" DIP Reducer	1	EA		
63	WSACC	8" Gate Valve w/ Valve Box	1	EA		
64	WSACC	8" TEAM Insertion Valve w/ Valve Box	1	EA		



High Performance Living



635 Alfred Brown Jr. Court SW, P.O. Box 308, Concord, NC 28026 – www.concordnc.gov

No.	Item	Description	Qty.	Units	Unit Price (\$)	Item Total (\$)
65	WSACC	6" TEAM Insertion Valve w/ Valve Box	1	EA		
66	WSACC	18" by 0.250" Thick Steel Casing w/ Stainless Steel Spiders	67	LF		
67	WSACC	Fire Hydrant Assembly	1	EA		
68	WSACC	6" Gate Valve w/ Valve Box	1	EA		
69	WSACC	Connection to Existing Watermains	1	LS		

TOTAL BASE COST \$ _____

10% CONTINGENCY \$ _____

TOTAL COST \$ _____

Engineering

Phone (704) 920-5425 • Fax (704) 786-4521

2. Acknowledge Addendum 1 on the bid form of the documents.

End of Addendum 1