

ADDENDUM 1

LES MYERS PARK TENNIS COURTS RECONSTRUCTION - REBID PROJECT NO. 2023-009 – BID # 2575

April 20, 2023

1) Addition of Scope of Work page to rebid documents that was inadvertently left out:

PROJECT SCOPE

The City of Concord proposes to reconstruct/resurface 6 all-weather tennis courts at Les Myers park.

Contractor - Furnish the labor, materials, equipment, and services necessary to reconstruct/resurface 6 all-weather tennis courts.

- Site Work:

- 1. Remove all fence mesh and fence posts as necessary to allow truck access to courts.
- 2. Remove and haul away net post bases.
- 3. Demolish existing Asphalt surface and haul off site.
- 4. Install two (2) inches of ABC stone over existing stone base as necessary for grading.

- Construction:

- 1. Fine grade stone base with laser and compact.
- 2. Place and compact 3" NCDOT S9.5A asphalt surface within standard slope.
- 3. Replace all fence and poles that were removed.
- 4. Install new net posts PVC sleeves and center anchor.

New asphalt must cure for a minimum of 30 days before any coatings are applied.

- <u>Patching</u>: All areas holding 1/8 inch of water for more than one hour after flooding on a sunny 70-degree day shall be patched with acrylic patch binder. All patches will be sanded level with surrounding court area.

- <u>Acrylic Resurfacer</u>: Over the entire court area, apply **two (2) coats** of Sport Master Acrylic Resurfacer

-Acrylic Color Coat: Apply two (2) coats of Sport Master Color Coat.

- <u>Court Lines</u>: Layout, mask and hand paint playing lines with Sport Master T/C white line paint. All 6 courts to include 10 and under lines.

-Completion of Court:

Provide and install six (6) pair of net posts and six (6) 3.5 double top tapered nets (5-year manufacturer's warranty) with center straps. Clean up area and dispose of all debris. Leave courts ready for play.

<u>Weather Limitations</u>: No part of the Sportmaster surfacing system may be conducted during rain or when rain is imminent. Air and surface temperature must be at least 50 degrees for a 24hr period and not more than 130 degree surface temperature.

Other Requirements: Owner shall provide access for all Equipment and an Area adjacent to the sight for storing and prepping of materials. Owner shall be responsible for providing water and electric on sight for the mixing of materials, must be within 100ft of each court.

Warranty: Contractor, shall warranty the completed courts to be free of significant defects in workmanship and materials for a period of one (1) year. The warranty shall commence on the date of completion, but will not be enforceable, unless payment is made in the full amount of the executed contract, including change orders and late payment fees (if applicable).

2) Acknowledge receipt of ADDENDUM 1 on all bid documents.

End of Addendum 1