

ADDENDUM 1

City of Concord Transportation Department Building Upfit

September 16, 2021

1. Plans have been updated with changes. This link can be used to obtain the updated version of the plans on the City of Concord Website:

<https://concordnc.gov/Departments/Finance/Purchasing/RFPs-RFQs-and-Bids> . The updated plans incorporate the following changes:

- The HVAC UV lighting will need to be the American Light & Power CK 48” dual light kits one for each unit instead of the Honeywell which are too short for the units. They are to be installed between the indoor coil and blower. Contact Ivan at AL&P 18433060070 for ordering information. The Honeywell round D690 damper is no longer available so the Greenheck equivalent needs to be used.
- The color of the lights was listed as 5K. All COC Buildings are 35k or 4k.
- Bypass dampers for the VVT Zone Systems have been added.
- The hot water heater has been relocated from Storage 113 to Janitor Closet 104.

2. Room #'s 109 & 110 have LVT listed for the flooring. Flooring for these rooms will need to be carpet.

3. The backsplash in the main breakroom is listed as FRP on page A-7. The backsplash needs to be Festival Bright White Ice 4” wall tile instead of FRP.

4. Bidder will need to acknowledge the receipt of Addendum 1 dated 9/16/2021 on the bid form for this project.

End of ADDENDUM 1